BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Rajarajeshwari Nagara Division, RR Nagara Zone, B.B.M.P., Bangalore.

Tender Notification No: EE/RRND/Tend/20/2020-21 Date: 29.03.2021

Indet No: BBMP/2020-21/OW/WORK_INDENT42853/CALL-2

SCHEDULE -B

Name of Work: Improvement of UGD (Under Ground Drainage) Lines in J P park in ward 17

Sl.No	Qty	Description of work	Unit	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	255.00	KSRB 2-2 : Earthwork excavation by manual means for foundation of buildings, water supply and sanitary lines and electrical conduits etc, either in pits or in trenches 1.5m and above in width, in soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods complete as per specifications. in ordinary soil.	Cum	332.66	Rupees Three Hundred Thirty Two And Paise Sixty Six Only
2	219.96	KSRB 2-2 : Earthwork excavation by manual means for foundation of buildings, water supply and sanitary lines and electrical conduits etc, either in pits or in trenches 1.5m and above in width, in soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods complete as per specifications. in hard soil.	Cum	499.55	Rupees Four Hundred Ninety Nine And Paise Fifty Five Only
3	292.00	KSRB 12-1 : Providing and laying in position to required level or slope of internal diameter salt glazed stoneware pipes grade A and jointing with stiff mixture of cement mortar in proportion of 1:1, testing of pipes and joints,including cost of materials, labour charges complete as per specifications. 300mm	Mtrs	702.04	Rupees Seven Hundred Two And Paise Four Only
4	18.00	KSRB 12-5 : Constructing brick masonry circular type manhole 1.22 m internal dia at bottom and 0.56m dia at top, with table moulded and non modular bricks of class designation 50 in cement mortar 1:4, inside cement plaster 12mm thick with cement mortar 1:3, finished with a floating coat of neat cement, foundation concrete M 10 using 40mm and down size granite metal and making necessary channel in cement concrete M 15 with 20mm and down size granite metal, finished with a floating coat of neat cement, with S.F.R.C. cover and frame (heavy duty, HD-20 grade designation) 560mm nternal diameter confirming to IS :12592, total weight length of cover and frame to be not less than 182 kg, fixed in cement concrete M 15 20mm and down size broken granite metal, providing and removing centering, shuttering including cost of materials, labour charges, HOM complete as per specifications. (Excavation, footrests and 12mm thick cement plaster on the external surface shall be paid separately) Specification No. KBS 12.4 11.39 KSRB 12-5.3 2.29m deep	Nos	38776.61	Rupees Thirty Eight Thousand Seven Hundred Seventy Six And Paise Sixty One Only
5	178.50	KSRB 2-4 : Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5 m. including cost of all labour complete as per specifications.	Cum	134.62	Rupees One Hundred Thirty Four And Paise Sixty Two Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

6	21.90	KKSRB 4-1.3 : Providing and laying in position plain cement concrete of Mix 1:4:8 with OPC @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM	Cum	5676.36	Rupees Five Thousand Six Hundred Seventy Six And Paise Thirty Six Only
7	13.14	KSRB 4-1.6 ; Providing and laying in position plain cement concrete of Mix 1:2:4 with OPC @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregtes @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications.	Cum	6032.39	Rupees Six Thousand Thirty Two And Paise Thirty Nine Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP